

### **3.SCHEDULE OF QUANTITIES**

## SCHEDULE OF QUANTITIES

<b>Name of the Work: Construction of cement concrete Side Berm on both sides of the campus road of NIT Meghalaya at Sohra (Cherrapunjee)</b>					
<b>Sl. No</b>	<b>Description Of Items</b>	<b>Qty.</b>	<b>Unit</b>	<b>Rates to be quoted in figure &amp; words (Rs)</b>	<b>Amount(Rs.)</b>
1	Providing Soling with stone/ best quality picked jhama brick, sand packed and laid to level and in panel after preparing the sub grade as directed including all labour and materials and if necessary dewatering, complete.	7770.00	Sqm		
	Stone Soling				
	100 mm				
2	Plain cement concrete works in foundation bed for footing steps, walls, brick works etc below plinth level as directed and specified including dewatering if necessary, and curing complete (shuttering where necessary shall be measured and paid separately)	777.00	Cum		
	1:2:4				
3	20mm cement plaster of mix	7770.00	Sqm		
	1:4 (1 cement: 4 fine sand)				
<b>Total Quoted Amount = Rs</b>					

*Rupees in words*

*Dated signature of the Tenderer with Seal*